BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2022-23/OW/WORK_INDENT51418

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/01/2022-23, Date: 21-04-2022

Name of Work:Filling of Pot holes in Ward No. 09, (Vidyaranyapura). For the year 2021-22.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Sambashiva ( )	
				In Figures	In Words
1	428	Wet Mix Macadam KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications	Cum	1701.0	Rupees One Thousand Seven Hundred One Only
2	2853.32	Filling Pot-holes and Patch Repairs with Bituminous Concrete, 40 mm KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, filling back the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications	Sqm	276.0	Rupees Two Hundred Seventy Six Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92